

AD-A088 779

BAKER (MICHAEL) JR INC BEAVER PA

F/G 13/13

NATIONAL DAM INSPECTION PROGRAM. UNNAMED TRIBUTARY TO HARMON CR--ETC(U)

JUL 80 J A DZIUBEK


DACW31-80-C-0025

NL

UNCLASSIFIED

1 OF 1  
40  
50-10-113

END  
DATE  
FILMED  
10-80  
DTIC



MICROCOPY RESOLUTION TEST CHART  
 NATIONAL BUREAU OF STANDARDS-1963-A


**OHIO RIVER BASIN  
UNNAMED TRIBUTARY TO HARMON CREEK, WASHINGTON COUNTY  
PENNSYLVANIA**

**PA 480**

**NDI No. PA 01125  
POMDER No. 63-84  
SCS No. PA 480**

AD A08879

**PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM  
PACW31-FO-C-0025**



*prepared for*

**DEPARTMENT OF THE ARMY  
Baltimore District, Corps of Engineers  
Baltimore, Maryland 21203**

*prepared by*

**MICHAEL BAKER, JR., INC.**

**Consulting Engineers  
4301 Dutch Ridge Road  
Beaver, Pennsylvania 15009**

**July 1980**

**ORIGINAL CONTAINS COLOR PLATES; ALL DDC  
REPRODUCTIONS WILL BE IN BLACK AND WHITE.**

**80 8 27 064**

**DTIC  
ELECTE  
SEP 8 1980**

**INC FILE COPY**

**THIS DOCUMENT IS BEST QUALITY AVAILABLE  
FOR PUBLIC RELEASE AND USE IN  
REPRODUCTION MATERIALS**

**FOR DOCUMENT USE ONLY  
NO PUBLIC RELEASE AND USE IN  
REPRODUCTION MATERIALS**

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**

OHIO RIVER BASIN

WASHINGTON COUNTY, COMMONWEALTH OF PENNSYLVANIA  
NDI No. PA 01125  
PennDER No. 63-84  
SCS No. PA 480

⑥ PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

Unnamed Tributary to Harmon Creek

NDI Number PA-01125. Dam No. 63-84.

21st Number 14-00. Ohio River E.

Washington County, Pennsylvania.

Phase I Inspection Report

Prepared for: DEPARTMENT OF THE ARMY  
Baltimore District, Corps of Engineers  
Baltimore, Maryland 21203

Prepared by: MICHAEL BAKER, JR., INC.  
Consulting Engineers  
4301 Dutch Ridge Road  
Beaver, Pennsylvania 15009

DTIC  
ELECTE  
SEP 8 1980  
S D C  
1287

11/17 Jul 81

15  
DA 0131-84-C-pp251

10 John A. L. Zwick

This document has been approved  
for public release and sale; its  
distribution is unlimited.

415715

**i**

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I Inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Classification For

OFFICIAL

OC TAB

unannounced  
justification by  
*for 50*  
*on file*

distribution

Availability Codes

Available/or  
special

at

A

23

PHASE I REPORT  
NATIONAL DAM INSPECTION PROGRAM

PA 480, Washington County, Pennsylvania  
NDI No. PA 01125, PennDER No. 63-84, SCS No. PA 480  
Unnamed Tributary to Harmon Creek  
Inspected 27 March 1980

ASSESSMENT OF  
GENERAL CONDITIONS

PA 480 is classified as an "Intermediate" size - "Significant" hazard dam. The dam, owned by the Washington County Commissioners, is used to reduce floodwater damages in the Harmon Creek Watershed. The dam and appurtenant structures were found to be in good overall condition at the time of inspection.

Hydraulic/hydrologic evaluations, performed in accordance with procedures established by the Baltimore District, U.S. Army Corps of Engineers, for Phase I Inspection Reports, revealed that the spillway will pass the Probable Maximum Flood (PMF) without overtopping the dam. A spillway design flood (SDF) in the range of the 1/2 Probable Maximum Flood (1/2 PMF) to the PMF is required for PA 480. The 1/2 PMF was selected as the SDF. The spillway is therefore considered to be "adequate".


The visual inspection and review of information revealed only one problem which requires remedial action by the owners of the dam at the present time; namely, the repair of an erosion channel which has developed parallel to the rock gutter running along the downstream side of the embankment at the junction of the embankment and the emergency spillway.

It is also recommended that the slumping areas on the right abutment and the small slump at the downstream end of the emergency spillway be monitored in future inspections to ensure that these conditions do not become serious.

In addition, the following operational measures are recommended to be undertaken by the owner:

- 1) Develop a detailed emergency operation and warning system.
- 2) During periods of unusually heavy rainfall, provide around-the-clock surveillance of the dam.
- 3) When warning of a storm of major proportions is given by the National Weather Service, the owner should activate the emergency operation and warning system.

PA 480



Submitted by:

MICHAEL BAKER, JR., INC.

John A. Dziubek  
John A. Dziubek, P.E.  
Engineering Manager-Geotechnical

Date: 10 July 1980


Approved by:

DEPARTMENT OF THE ARMY  
BALTIMORE DISTRICT, CORPS OF ENGINEERS


James W. Peck  
JAMES W. PECK  
Colonel, Corps of Engineers  
District Engineer

Date: 11 August 80





Overall View of the Upstream Face of the Dam from the Right Abutment



Overall View of the Downstream Face of the Dam from the  
Emergency Spillway

## TABLE OF CONTENTS

	<u>Page</u>
Section 1 - Project Information	1
Section 2 - Engineering Data	7
Section 3 - Visual Inspection	9
Section 4 - Operational Procedures	11
Section 5 - Hydraulic/Hydrologic	12
Section 6 - Structural Stability	14
Section 7 - Assessment, Recommendations/Remedial Measures	17

## APPENDICES

Appendix A - Visual Inspection Check List, Field Sketch, Top of Dam Profile, and Typical Cross-Section
Appendix B - Engineering Data Check List
Appendix C - Photograph Location Plan and Photographs
Appendix D - Hydrologic and Hydraulic Computations
Appendix E - Plates
Appendix F - Regional Geology

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM  
PA 480

NDI No. PA 01125, PennDER No. 63-84, SCS No. PA 480

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

- a. Authority - The Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.
- b. Purpose of Inspection - The purpose of the inspection is to determine if the dam constitutes a hazard to human life or property.

1.2 DESCRIPTION OF PROJECT

- a. Description of Dam and Appurtenances - PA 480 was designed by the U.S. Department of Agriculture, Soil Conservation Service (SCS) for floodwater detention. The total length of the dam is 555 feet, including the emergency spillway on the right abutment. The maximum height of the dam is 66 feet and the minimum crest elevation is 1010.0 feet Mean Sea Level (M.S.L.). The top width of the dam is 20 feet. The slope of the upstream face of the embankment is 3H:1V (Horizontal to Vertical) and the slope of the downstream face is 2.5H:1V. There are two benches on the upstream face of the embankment. The first is 18 feet wide and is located between Elevations 968.0 feet and 969.0 feet M.S.L. The second is 10 feet wide and is located between Elevations 990.9 feet and 991.8 feet M.S.L. There is also a 10 foot wide bench on the downstream side of the dam between Elevations 973.0 feet and 973.6 feet M.S.L.<sup>1</sup>

<sup>1</sup>These elevations correspond to the location of the benches at a cross-section taken through field inspection Station 1+29 on the top of dam profile (Appendix D). The benches have a 1 percent slope towards the left abutment so actual bench elevations vary along the dam. Field inspection stationing refers to the stationing used by Michael Baker, Jr., Inc. during the visual inspection. This stationing is shown on the field sketch. The SCS design stationing refers to the stationing found on the design plates in Appendix E.

The embankment was constructed using two zones of earthfill. The core section of the dam, zone I, consists of relatively impervious materials (CL, CH, and ML). This core has 2H:1V side slopes, a top width of 20 feet, and extends to Elevation 997.1 feet M.S.L. (12.9 feet below the design top of dam elevation, 1010.0 feet M.S.L.). The outer shell of the embankment, zone II, consists of fractured and weathered shale (classified GC) material. Zone II also consists of various materials excavated from the emergency spillway.

The drainage system for the embankment has several components: (1) a chimney drain between the downstream face of the zone I material and the zone II material, (2) a foundation drain trench, (3) a blanket drain, and (4) a toe drain (see Plate 7).

A grout curtain was placed in the right abutment in a zone of high permeability. This curtain extends for a total of 239 feet; from SCS design Station 5+46 to 7+85 (see Plate 8 for details).

The principal spillway is a drop-inlet structure consisting of a two-stage reinforced concrete riser connected to a 30 inch diameter reinforced concrete outlet pipe. The low-level inlet on the concrete riser is a 9 inch high by 15 inch wide orifice with an invert elevation of 968.0 feet M.S.L. This inlet maintains the normal pool level at Elevation 968.0 feet M.S.L. There is 25.1 acre-feet of storage at normal pool level, all of which is reserved for a 50-year accumulation of sediment.

The upper-level intake consists of two concrete overflow weirs with rounded downstream edges. The weirs are located on either side of the riser unit. The crest of these weirs is at Elevation 980.7 feet M.S.L., 12.7 feet above the invert of the low-level intake. Each weir is 7.5 feet long and there is a rectangular opening 1.25 feet high by 7.5 feet long above each weir. The openings to the upper and low-level intakes are protected by metal trash racks.

The 30 inch outlet pipe from the riser unit is 330 feet long and has 11 concrete anti-seep collars. The pipe exits into a concrete impact basin at the downstream toe of the embankment.

There is an 18 inch diameter reservoir drain pipe which extends from the base of the riser unit into the reservoir. The entrance invert of this pipe is at Elevation 948.2 feet M.S.L. The pipe is controlled by an 18 inch slide gate which is operated by a control located on the top of the riser unit.

The emergency spillway for the dam is located at the right abutment. It consists of a trapezoidal channel with a bottom width of 30 feet. The right side of the channel has a 2H:1V side slope and the left side has a 3H:1V side slope.

- b. Location - PA 480 is located on an unnamed tributary to Harmon Creek, approximately 3.5 miles southwest of Burgettstown, Pennsylvania. The dam and reservoir are in Jefferson Township, Washington County, Pennsylvania and can be located on the Avella, Pennsylvania USGS 7.5 minute topographic quadrangle. The coordinates of the dam are N 40° 21.9' and W 80° 27.6'.
- c. Size Classification - PA 480 has a maximum height of 66 feet and a top of dam storage capacity of 418.8 acre-feet. The dam is therefore in the "Intermediate" size category.
- d. Hazard Classification - There are two frequently used railroad lines 1800 feet downstream from the dam. These lines and several homes located approximately 6000 feet downstream from the dam would suffer economic damage if the dam were to fail. No loss of life is likely to result from a dam failure. The dam is therefore in the "Significant" hazard category.
- e. Ownership - The dam and reservoir are owned by the Washington County Commissioners, Washington County Courthouse, Washington, Pennsylvania.
- f. Purpose of Dam - The dam is one of several floodwater retarding dams constructed by the SCS in the Harmon Creek Watershed. Its purpose is to reduce floodwater damages in downstream areas of the watershed.
- g. Design and Construction History - Design of PA 480 was completed in 1965 by the SCS. Some minor revisions to the hydraulic design of the structure were made in 1971. Gal of Charleroi, Pennsylvania and Solomon-Teslovich of Masontown, Pennsylvania

were the contractors responsible for constructing the dam. Work was begun in March 1978 and fully completed in the spring of 1979.

- h. Normal Operating Procedures - The pond is typically controlled by the low-level inlet of the riser structure at Elevation 968.0 feet M.S.L. Washington County and SCS personnel inspect the dam each year according to the procedures for annual inspections of SCS dams of this type. Washington County personnel perform routine maintenance on the dam.

### 1.3 PERTINENT DATA

- a. Drainage Area (square miles) - 1.09
- b. Discharge at Dam Site (c.f.s.) -
- Peak Outflow at -
- |   |      |
|---|------|
| Crest of Riser (El. 980.7 ft. M.S.L.) -                           | 15.9 |
| Crest of Emergency Spillway<br>(El. 997.1 ft. M.S.L.) -           | 139  |
| Design High Water (El. 1000.2 ft. M.S.L.) -                       | 627  |
| Top of Dam (El. 1010.0 ft. M.S.L.) -                              | 6846 |
| Maximum Flood of Record (El. 970.9 ft.<br>M.S.L., date unknown) - | 7    |
- c. Elevation (feet above M.S.L.) -
- |                               |        |
|-------------------------------|--------|
| Design Top of Dam -           | 1010.0 |
| Maximum Design Pool -         | 1000.2 |
| Emergency Spillway Crest -    | 997.1  |
| Crest of Upper-Level Outlet - | 980.7  |
| Invert of Low-Level Outlet -  | 968.0  |
| Normal Pool -                 | 968.0  |
| Exit Invert of Outlet Pipe -  | 944.0  |
- d. Reservoir (feet) -
- |   |      |
|---|------|
| Length of Normal Pool (El. 968.0 ft.<br>M.S.L.) -   | 815  |
| Length of Maximum Pool (El. 1010.0 ft.<br>M.S.L.) - | 1700 |
- e. Storage (acre-feet) -
- |   |       |
|---|-------|
| Top of Dam (El. 1010.0 ft. M.S.L.) -          | 418.8 |
| Maximum Design Pool (El. 1000.2 ft. M.S.L.) - | 253.0 |

Crest of Emergency Spillway (El. 997.1 ft. M.S.L.) -	212.3
Normal Pool (El. 968.0 ft. M.S.L.) -	25.1 <sup>2</sup>

f. Reservoir Surface (acres) -

Top of Dam (El. 1010.0 ft. M.S.L.) -	19.4
Maximum Design Pool (El. 1000.2 ft. M.S.L.) -	14.6
Crest of Emergency Spillway (El. 997.1 ft. M.S.L.) -	13.3
Normal Pool (El. 968.0 ft. M.S.L.) -	3.6

g. Dam -

Type - Zoned earthfill embankment

Length (feet) -	555
Height (feet) -	66
Crest Width (feet) -	20

Slopes - Upstream - 3H:1V. There is an 18 foot wide bench between Elevations 968.0 feet and 969.0 feet M.S.L. and a 10 foot wide bench between Elevations 990.9 ft. and 991.8 ft. M.S.L.

Downstream - 2.5H:1V with a 10 foot wide bench between Elevations 973.0 ft. and 973.6 ft. M.S.L.

Zoning - The inner core of the embankment (zone I) was constructed using relatively impervious materials (CL, CH, ML). This core has 2H:1V side slopes, a top width of 20 feet, and extends to Elevation 997.1 feet M.S.L. The outer shell (zone II) consists of fractured and weathered shale (classified GC) material. Zone II also consists of various materials excavated from the emergency spillway.

Cut-off - Zone I material was used to fill the cut-off trench which extends under the entire embankment. The trench is a minimum of 3.4 feet deep, has 2H:1V side slopes, and has a bottom width ranging from 12 to 25 feet.

Grout Curtain - A grout curtain was placed in the right abutment in a zone of high permeability. This curtain extends for

<sup>2</sup>This storage volume is reserved for a 50-year accumulation of sediment. It is not included in floodwater storage computations.

a total of 239 feet; from SCS design Station 5+46 to 7+85<sup>3</sup> (see plate 8 for details).

Drains - The drain system for the dam consists of a chimney drain between the downstream face of the zone I material and the zone II material, a foundation drain trench, a blanket drain, and a toe drain. Rock gutters were also placed at the junction of the embankment and emergency spillway and at the junction of the embankment and left abutment to provide surface drainage.

h. Diversion and Regulatory Tunnel - None

i. Spillway (Emergency Spillway) -

Type - Trapezoidal earth and rock cut channel at the right abutment

Length (feet) - 460

Bottom Width (feet) - 30

Side Slopes - Against Right Abutment - 2H:1V

Towards Dam - 3H:1V

Crest Elevation (feet M.S.L.) - 997.1

j. Regulatory Outlets (Principal Spillway) - The principal spillway is a drop-inlet structure consisting of a two-stage reinforced concrete riser connected to a 30 inch outlet pipe. The low-level inlet is a 9 inch by 15 inch orifice (invert Elevation 968.0 ft. M.S.L.). The upper level intake consists of two concrete overflow weirs (crest Elevation 980.7 ft. M.S.L.) with a total weir length of 15 feet. There is also an 18 inch reservoir drain pipe extending from the base of the riser unit into the reservoir. This drain pipe is controlled by an 18 inch slide gate which is operated by a control located on the top of the riser unit.

<sup>3</sup>The SCS stationing shown on the plate included in Appendix E differs from that shown on the field sketch prepared during the inspection. Unless specific reference is made to SCS stations, stations used in this report refer to the stationing shown on the field sketch and top of dam profile in Appendix A.



## SECTION 2 - ENGINEERING DATA

### 2.1 DESIGN

PA 480 was designed by the SCS as a single purpose flood prevention structure. It is one of eight flood control dams in the Harmon Creek Watershed. It was designed to retard the 100-year frequency storm without discharge occurring in the emergency spillway.

PA 480 was designed according to standard SCS procedures for structures of this type. Information reviewed for this report included the following:

- 1) SCS Drawings No. PA 480-P, "Harmon Creek Watershed Project, Floodwater Retarding Dam PA 480, Brooke and Hancock Counties, West Virginia, Washington County, Pennsylvania," 43 sheets, 1976.
- 2) "Design Report, Site PA 480, Harmon Creek Watershed, Pennsylvania," U.S. Department of Agriculture, Soil Conservation Service, undated.
- 3) The correspondence file containing the permit application for the dam and inspection reports filed by the Pennsylvania Department of Environmental Resources' (PennDER) personnel during construction of the dam.

"As built" plans have not yet been completed for this dam.

### 2.2 CONSTRUCTION

PA 480 was built by Gal of Charleroi, Pennsylvania and Soloman-Teslovich of Masontown, Pennsylvania. Construction was begun in March 1978 and all work except for construction of the riser unit and placement of the rock gutters between the right abutment and embankment was completed by December 1978. This remaining work was completed in the spring of 1979.

No significant problems were reported by SCS or PennDER personnel during the construction of the dam.

### 2.3 OPERATION

The reservoir level is typically maintained by the low-level inlet of the riser structure at Elevation 968.0 feet M.S.L. Washington County and SCS personnel inspect the

dam each year according to the procedures for annual inspections of SCS dams of this type. Routine maintenance is performed by Washington County personnel.

2.4 EVALUATION

- a. Availability - The information reviewed is readily available from the SCS office in Harrisburg, Pennsylvania and PennDER's File No. 63-84.
- b. Adequacy - The information available is adequate for a Phase I inspection of this dam.
- c. Validity - There is no reason at the present time to question the validity of the available information.

## SECTION 3 - VISUAL INSPECTION

### 3.1 FINDINGS

- a. General - The visual inspection was performed on 27 March 1980. There had been relatively heavy rainfall in the area on the days immediately preceding the inspection. However, no unusual weather conditions were experienced during the inspection and the reservoir level was at Elevation 968.9 feet M.S.L., 0.9 foot above normal pool. The dam and appurtenant structures were found to be in good condition at the time of the inspection. Noteworthy observations made during the visual inspection are described in the following paragraphs. The complete visual inspection check list, field sketch, top of dam profile, and typical cross-section are presented in Appendix A.
- b. Dam - The following is a list of the minor deficiencies observed during the visual inspection of the embankment and abutments.
  - 1) There are several areas on the right abutment above the emergency spillway where there is some minor erosion and sloughing of the abutment slopes taking place. This problem is at least partially caused by groundwater seepage from the area behind the abutment and exposed zones of soft weathered mudstone. A number of small springs were observed on the abutment, all of which were flowing less than 1 g.p.m. This seepage had saturated the abutment slope in several locations. On the three benches above the emergency spillway, there was some ponded water which probably collected during recent rainfall. This condition is not believed to be a serious problem at the present time.
  - 2) A small erosion channel has developed parallel to the rock gutter which runs along the downstream side of the embankment at the junction of the embankment and the emergency spillway.
  - 3) Some ponded water was observed on the bench on the downstream side of the embankment. Several areas on the embankment below this bench were relatively saturated. Because the

bench was approximately 4 feet higher than the pool level at the time of the inspection, this water was probably the result of recent precipitation and not seepage through the embankment.

- c. Appurtenant Structures - Both the concrete riser unit and impact basin were in good condition at the time of the inspection. There was a small slump at the downstream end of the emergency spillway.
- d. Reservoir Area - The slopes of the reservoir and watershed are relatively steep. The area above the right abutment is the site of a strip mine. The remainder of the watershed is primarily forests with some pastureland.

There were several areas in the watershed where some sloughing of the steeper slopes had taken place. This should not present a significant problem for the dam or reservoir.

The dam was designed to provide storage for a 50-year accumulation of sediment. There was no evidence which indicated that sedimentation was occurring at a faster rate than that anticipated by the SCS.

- e. Downstream Channel - The slopes of the downstream channel are moderate. There is a one-lane access road to the dam over the downstream channel approximately 200 feet downstream from the dam. Two 48 inch pipes carry flow under the road embankment. There are also 2 railroad lines 2000 feet downstream from the dam. The railroad lines are on embankments which are approximately 30 feet high. Flow under the embankments is carried by a 5 foot by 5 foot box culvert.

Several homes are located approximately 6000 feet downstream from the dam.

## SECTION 4 - OPERATIONAL PROCEDURES

### 4.1 PROCEDURES

The dam and appurtenances are inspected by Washington County and SCS personnel each year according to the procedures for annual inspections of SCS dams of this type. Formal maintenance and inspection procedures are presented in the "Erosion and Sediment Control Plan" for the dam.

### 4.2 MAINTENANCE OF DAM AND APPURTENANCES

Routine maintenance is performed periodically by Washington County personnel. Formal maintenance procedures are described in the "Erosion and Sediment Control Plan" for this dam. At the present time, maintenance of the dam and appurtenances is considered to be adequate.

### 4.3 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

An emergency warning procedure is being developed for PA 480. However, at the present time, no formal procedure is in effect.

### 4.4 EVALUATION OF OPERATIONAL ADEQUACY

The present operational and maintenance procedures for the dam are considered to be adequate. Formal emergency warning procedures should be developed and implemented.

## SECTION 5 - HYDRAULIC/HYDROLOGIC

### 5.1 EVALUATION OF FEATURES

- a. Design Data - Hydrologic and hydraulic design calculations for PA 480 were obtained from the SCS design report for this dam. The dam was designed to reduce floodwater damages in the Harmon Creek Watershed by retarding the 100-year frequency storm without discharge occurring in the emergency spillway. A sediment storage volume equal to a 50-year accumulation of sediment has been provided in the impoundment.

The design high water and top of dam elevations were determined by routing the emergency spillway and freeboard hydrographs developed by the SCS through the reservoir and dam. Both hydrographs were based on a storm duration of 6 hours. A summary of the rainfall and hydrograph data used in the design of the dam is presented in Appendix D.

- b. Experience Data - During the brief lifetime of the structure, there have been no major floods reported in the watershed. The elevation of a high water mark on the riser unit, Elevation 970.9 feet M.S.L. indicates the highest reservoir level was 2.9 feet above normal pool. This corresponds to a discharge of 7 c.f.s. from the principal spillway. The date at which this reservoir level was reached is unknown.
- c. Visual Observations - No conditions were observed during the visual inspection which would indicate that the dam and appurtenances could not perform satisfactorily during a flood event.
- d. Overtopping Potential - PA 480 is an "Intermediate" size - "Significant" hazard dam requiring evaluation for a spillway design flood (SDF) in the range of the 1/2 Probable Maximum Flood (1/2 PMF) to the Probable Maximum Flood (PMF). Because of the small size of the drainage area and because the dam is on the low end of the "Intermediate" size category, the 1/2 PMF was selected as the SDF. The SCS has designed the dam using an SDF essentially equal to the PMF (see Appendix D). After reviewing the calculations prepared by the SCS and judging them to be accurate, it was determined that further hydrologic and hydraulic analysis was unnecessary.

- e. Spillway Adequacy - The dam and reservoir, as outlined above, was designed based on a freeboard hydrograph essentially equal to the PMF. The spillway is therefore considered to be "adequate".

## SECTION 6 - STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

- a. Visual Observations - The minor slumping of the right abutment and the slump at the downstream end of the emergency spillway do not represent a threat to the continued structural stability of the dam at the present time.

It is recommended that the seepage and sloughing of the right abutment be monitored during future inspections to ensure that these conditions do not become serious.

- b. Design and Construction Data - Calculations of embankment slope and foundation stability were not available for review. However, a summary report from the SCS Soil Mechanics Laboratory at Lincoln, Nebraska dated 7 October 1971 presented the results of the laboratory soil testing program and slope stability analysis performed. Total stress shear strength parameters obtained and used in the slope stability analysis were reported as follows:

#### Foundation Materials -

Soil Type -	Clayey Sand (SC)
Type of Test Performed -	Direct Shear
Angle of Internal Friction ( $\phi$ ) -	42°
Cohesion (C) -	200 p.s.f.
Sample Type -	Undisturbed Shelby Tube Sample

(Note: The shear parameters were reduced to  $\phi = 35^\circ$  and  $c = 200$  p.s.f. for the stability analysis to approximate the total stress shear parameters because the parameters from the slow direct shear test approach the effective stress values.)

#### Zone I (core) Embankment Materials -

Soil Type -	Weathered Shale (CL)
Type of Test Performed -	Consolidated Undrained Triaxial Shear Test
Angle of Internal Friction ( $\phi$ ) -	20°
Cohesion (c) -	425 p.s.f.
Sample Type -	Minus No. 4 Sieve, Remolded and compacted at 100% Standard Proctor



Zone II (shell) Embankment Materials -

Soil Type -	Shale (CL)
Type of Test Performed -	Consolidated Undrained Triaxial Shear Test
Angle of Internal Friction ( $\phi$ ) -	15.5°
Cohesion (c) -	425 p.s.f.
Sample Type -	Minus No. 4 Sieve, Remolded, and compacted at 95% Standard Proctor

The results of 12 stability calculations (using a Modified Swedish Circle Method) was presented. The resulting minimum factor of safety for the upstream slope under full drawdown conditions was 1.35 with an 18 foot wide berm at Elevation 968.0 feet M.S.L. and 3H:1V slope. The geometry of the upstream slope was later revised to include an additional 10 foot wide berm at Elevation 989.0 feet M.S.L. The resulting minimum factor of safety for the downstream slope (2.5H:1V) under steady state seepage was 1.48 with a 10 foot wide berm at Elevation 970.0 feet M.S.L. and a drain at  $c/b = 0.6$  (or at a distance 0.6 times the base length of the downstream slope downstream from the vertical plane of the downstream edge of the crest of the dam). The embankment internal drainage design was later revised to place the drain at  $c/b = 0.7$  and to include a chimney drain, a drainage blanket, and a toe drain. The chimney drain was installed primarily for additional stability.

Based upon the above information, coupled with the visual inspection, it is concluded that further stability assessments of the embankment are not necessary.

The right abutment consists of shale, siltstone, sandstone, and limestone. Some of the very soft, highly weathered shale and siltstone were considered to be a calcereous mudstone. These soft zones varied in thickness and slickensides were found in these deposits during the boring program. It was these soft zones which caused localized slumping and sliding in the emergency spillway after excavation because of fractures opening up due to rebound and change in the water table pattern. With time, additional slumping and sliding will occur in the emergency spillway area due to continued softening of the exposed areas of the mudstone. It is estimated that these localized slumps will not

interfere with the functioning of the emergency spillway but should be observed periodically to insure that the emergency spillway channel remains completely open.

- c. Operating Records - Nothing in the operating information available indicates cause for concern relative to the structural stability of the dam.
- d. Post-Construction Changes - No changes adversely affecting the structural stability of the dam have been performed.
- e. Seismic Stability - The dam is located in Seismic Zone 1 of the "Seismic Zone Map of the Contiguous United States", Figure 1, page D-30, "Recommended Guidelines for Safety Inspection of Dams". This is a zone of minor seismic activity. Therefore, further consideration of the seismic stability is not warranted.

## SECTION 7 - ASSESSMENT, RECOMMENDATIONS/REMEDIAL MEASURES

### 7.1 DAM ASSESSMENT

- a. Safety - The dam and its appurtenant structures were found to be in good overall condition at the time of the inspection. PA 480 is an "Intermediate" size - "Significant" hazard dam requiring evaluation for an SDF in the range of the 1/2 PMF to PMF. Because of the relatively small size of the drainage area and because the dam is on the low end of the "Intermediate" size category, the 1/2 PMF was selected as the SDF. As was discussed in Section 5, the spillway and reservoir were determined to be of sufficient size to safely pass the SDF without overtopping the dam. The spillway is therefore considered to be "adequate".
- b. Adequacy of Information - The information available is considered to be adequate for a Phase I Inspection Report.
- c. Urgency - No urgent remedial work is required. The owners of the dam should undertake the minor repair item described in Section 7.2 as soon as possible.
- d. Necessity for Additional Data/Evaluation - No conditions were observed during the inspection of this dam which would warrant additional evaluation at this time.

### 7.2 RECOMMENDATIONS/REMEDIAL MEASURES

The inspection revealed only one deficiency which should be corrected as soon as possible, namely, the repair of the erosion ditch described in paragraph 3.1.b., item 2.

It is also recommended that the slumping areas on the right abutment and the small slump at the downstream end of the emergency spillway be monitored in future inspections to ensure that these conditions do not become serious.

In addition, the following operational measures are recommended to be undertaken by the owner:

- 1) Develop a detailed emergency operation and warning system.

- 2) During periods of unusually heavy rainfall, provide around-the-clock surveillance of the dam.
- 3) When warning of a storm of major proportions is given by the National Weather Service, the owner should activate the emergency operation and warning system.

APPENDIX A

VISUAL INSPECTION CHECK LIST, FIELD SKETCH,  
TOP OF DAM PROFILE, AND TYPICAL CROSS-SECTION

Phase 1  
Visual Inspection  
Check List

Name of Dam PA 480 County Washington State PA Coordinates Lat. N 40° 21.2'  
 NDI # PA 01125  
 PennDer # 63-84  
 SCS # PA 480 Long. W 80° 27.6'  
 Date of Inspection 27 March 1980 Weather Sunny, clear Temperature 45° F.

Pool Elevation at Time of Inspection 968.9 ft.\* M.S.L. Tailwater at Time of Inspection 944.8 ft.\* M.S.L.  
 \*All elevations are referenced to the top of the riser unit, El. 982.8 ft. M.S.L.

Inspection Personnel:

Michael Baker, Jr., Inc.:  
James G. Ulinski  
Wayne D. Lasch  
George A. Slagle

Field Review (9 June 1980)

John A. Dziubek  
James G. Ulinski

NOTE: During the field review the pool was at the elevation of the second stage (El. 980.7 ft.) because of blockage of the low-level orifice. The Washington County Administrator and the Washington County SCS office were notified of the condition in order to take corrective action.

James G. Ulinski Recorder

CONCRETE/MASONRY DAMS - Not Applicable

Name of Dam: PA 480  
 NDI # PA 01125

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
LEAKAGE		
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS		
DRAINS		
WATER PASSAGES		
FOUNDATION		

CONCRETE/MASONRY DAMS - Not Applicable

Name of Dam: PA 480  
NDI # PA 01125

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES		
	STRUCTURAL CRACKING	
VERTICAL AND HORIZONTAL ALIGNMENT		
	MONOLITH JOINTS	
CONSTRUCTION JOINTS		



## EMBANKMENT

Name of Dam PA 480  
NDI # PA 01125

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

## SURFACE CRACKS

None observed

UNUSUAL MOVEMENT OR  
CRACKING AT OR BEYOND  
THE TOE

None observed

SLOUGHING OR EROSION OF  
EMBANKMENT AND ABUTMENT  
SLOPES

There are several areas on the right abutment above the emergency spillway where some minor erosion and sloughing of the abutment slopes have occurred. There is also a small slump at the downstream end of the emergency spillway. A small erosion channel has also developed parallel to the rock gutter which runs along the downstream side of the embankment at the junction of the embankment and the emergency spillway.

The minor sloughing of the right abutment is not considered to be a significant problem since the abutment has 11 ft. wide benches placed at three elevations. The small slump at the end of the emergency spillway is also not considered to be a significant problem at this time. The erosion channel should be repaired.

## EMBANKMENT

Name of Dam PA 480  
NDI # PA 01125

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

VERTICAL AND HORIZONTAL  
ALIGNMENT OF THE CREST

No problems were observed. See the top  
of dam profile at the end of this appendix.

RIPRAP FAILURES

Riprap used in the drainage trenches on the  
embankment and in the discharge channel is  
in good condition. No problems were observed.

VEGETATION

The embankment has a cover of grass, but  
the crown vetch and fescue has not yet  
developed.

## EMBANKMENT

Name of Dam PA 480  
NDI # PA 01125

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

JUNCTION OF EMBANKMENT  
AND ABUTMENT, SPILLWAY  
AND DAM

No problems observed

ANY NOTICEABLE SEEPAGE

Several minor seeps were observed on the right abutment above the emergency spillway. These seeps, none of which were flowing more than 1 g.p.m., are the result of groundwater flow. There was some ponding of water on the bench on the downstream side of the embankment. There were also several areas on the embankment below this bench in which the soil was saturated.

Seepage from the right abutment is contributing to the sloughing and erosion of the abutment. While this does not represent a problem at this time, these seeps and their effects on the stability of the abutment slopes should be monitored in future inspections. The ponded water on the bench on the downstream side of the embankment and the areas in which the soil was saturated are also not believed to be significant problems.

STAFF GAGE AND RECORDER None

DRAINS

No flow from the drains was observed.

## OUTLET WORKS

Name of Dam: PA 480  
NDI # PA 01125

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	All concrete surfaces were in good condition.	
INTAKE STRUCTURE	The intake structure was in good condition.	
OUTLET STRUCTURE	The concrete impact basin was in good condition.	
OUTLET CHANNEL	The outlet channel was clear of vegetation and debris. No problems were observed.	
EMERGENCY GATE	None	

## UNGATED SPILLWAY

Name of Dam: PA 480  
NDI # PA 01125

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

CONCRETE WEIR	None	
---------------	------	--

APPROACH CHANNEL	The emergency spillway consists of a vegetated trapezoidal earth channel at the left abutment. The vegetation has not yet fully covered the channel area.	
------------------	---	--

DISCHARGE CHANNEL	There was a small slump at the end of the emergency spillway. This is not considered to be a problem at this time.	
-------------------	--	--

BRIDGE AND PIERS	None	
------------------	------	--

A-9

GATED SPILLWAY - Not Applicable

Name of Dam: PA 480

NDI # PA 01125

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL		
APPROACH CHANNEL		
DISCHARGE CHANNEL		
BRIDGE AND PIERS		
GATES AND OPERATION EQUIPMENT		

INSTRUMENTATION - None

Name of Dam: PA 480  
 NDI # PA 01125

VISUAL EXAMINATION	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
--------------------	--------------	----------------------------

MONUMENTATION/SURVEYS

OBSERVATION WELLS

WEIRS

PIEZOMETERS

OTHER

## RESERVOIR

Name of Dam: PA 480  
NDI # PA 01125

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SLOPES	The slopes of the reservoir and watershed are relatively steep. There were several areas where sloughing of the slopes has occurred.	This is not considered to be a significant problem for the dam or reservoir.

## SEDIMENTATION

The reservoir was designed to allow for a 50-year accumulation of sediment. There was no evidence to suggest that sedimentation was occurring at a rate faster than that anticipated by the SCS.




## DOWNSTREAM CHANNEL

Name of Dam: PA 480  
NDI # PA 01125

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	<p>There is a one-lane bridge providing access to the dam over the downstream channel approximately 200 ft. downstream from the dam. Two 48 in. C.M.P.'s carry flow under the bridge. There are also two railroad lines approximately 2000 ft. downstream from the dam. The railroad lines are on embankments which are approximately 30 ft. high. Flow under the embankments is carried by a 5 ft. by 5 ft. box culvert.</p>	
SLOPES	The slope of the downstream channel is moderate.	
APPROXIMATE NO. OF HOMES AND POPULATION	<p>The closest homes are 6000 ft. downstream from the dam. Loss of life in these structures is not believed to be likely. There would be some economic damage to these homes.</p>	

SCHEMATIC: NOT TO SCALE



FIELD SKETCH

PA 480

NDI No. PA01125

Pennder No. 63-84

SCS No. PA480

INSPECTED 27 MARCH 1980

MICHAEL BAKER, JR., INC.

PA 480

A-14

THE BAKER ENGINEERS



28 April 1980

Box 280

Beaver, Pa. 15009

TOP OF DAM PROFILE  
TYPICAL CROSS-SECTION

DATE OF INSPECTION - 27 March 1980



APPENDIX B

ENGINEERING DATA CHECK LIST

ENGINEERING DATA  
CHECK LIST  
DESIGN, CONSTRUCTION, OPERATION

Name of Dam: PA 480  
NDI # PA 01175

ITEM	REMARKS
PLAN OF DAM	See Plate 3.

## REGIONAL VICINITY MAP

The Avella, Pennsylvania USGS 7.5 minute topographic quadrangle was used to prepare the regional vicinity map included as Plate 1 in this report.

## CONSTRUCTION HISTORY

Construction of the dam began in March 1978 and was completed in December 1978. The contractors involved in the construction of the dam were Gal, Charleroi, PA, and Solomon-Teslovich.

## TYPICAL SECTIONS OF DAM

See Plate 5 and Appendix A, Sheet 14.

## HYDROLOGIC/HYDRAULIC DATA

Design computations from the SCS design report for PA 480 were reviewed for this report. These computations are summarized in Section 5 and Appendix D.

## OUTLETS - PLAN

See Plate 9.

## - DETAILS

and

## CONSTRAINTS

See Plates 10 and 11.

- DISCHARGE RATINGS Discharge ratings were included in the SCS design report for this dam and are summarized in Appendix D.

RAINFALL/RESERVOIR RECORDS None available

Name of Dam: PA 480

NDI # PA 01125

B-2

ITEM	REMARKS
------	---------

**DESIGN REPORTS**

The SCS design report for PA 480 is available from the Harrisburg, PA SCS office.

**GEOLOGY REPORTS**

The required geology is presented in Appendix F. For a detailed report of the site geology, see the SCS design folder for PA 480.

**DESIGN COMPUTATIONS  
HYDROLOGY & HYDRAULICS  
DAM STABILITY  
SEEPAGE STUDIES**

These analyses are contained in the SCS design report for PA 480.

**MATERIALS INVESTIGATIONS  
BORING RECORDS  
LABORATORY  
FIELD**

The results of foundation and borrow excavation tests are contained in the SCS design report for PA 480.

**POST-CONSTRUCTION SURVEYS OF DAM**

None

**BORROW SOURCES**

The majority of the borrow material used for construction of the embankment was taken from the area above the right abutment and from the emergency spillway excavation. Further specifications of the borrow material are contained in the SCS design report for this dam.

Name of Dam: PA 480

B-3

NDI # PA 01125

ITEM	REMARKS
------	---------

**MONITORING SYSTEMS**

None

**MODIFICATIONS**

None

**HIGH POOL RECORDS**

The reservoir level has not yet risen to a significant amount above normal pool level.

**POST-CONSTRUCTION ENGINEERING  
STUDIES AND REPORTS**

None

**PRIOR ACCIDENTS OR FAILURE OF DAM  
DESCRIPTION  
REPORTS**

None

**MAINTENANCE  
OPERATION  
RECORDS**

Maintenance and operation records are kept in accordance with the operation and maintenance agreement.

B-4

Name of Dam: PA 480

NDI # PA 01125

ITEM	REMARKS
------	---------

SPILLWAY PLAN,

SECTIONS,  
and  
DETAILS

See Plates 3 and 4.

OPERATING EQUIPMENT  
PLANS & DETAILS

The only operating equipment for the dam is the valve which controls the reservoir drain pipe. Its location is shown on Plates 9 and 10.



CHECK LIST  
HYDROLOGIC AND HYDRAULIC DATA  
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: 1.09 sq. mi. (Primarily forests with  
some strip mining activity)

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 968.0 ft. M.S.L.  
(25.1 ac.-ft.)

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): 997.1 ft. M.S.L.  
(212.3 ac.-ft.)

ELEVATION MAXIMUM DESIGN POOL: 1000.2 ft. M.S.L. (253.0 ac.-ft.)

ELEVATION TOP DAM: 1010.0 ft. M.S.L.

SPILLWAY: (Emergency Spillway)

- a. Crest Elevation 997.1 ft. M.S.L.
- b. Type Vegetated trapezoidal earth and rock cut channel
- c. Bottom Width (Perpendicular to Flow) 30 ft. (bottom width)
- d. Length of Spillway along Centerline (Parallel to Flow) 460 ft.
- e. Location Spillover Right abutment
- f. Number and Type of Gates None

OUTLET WORKS: (Principal Spillway)

- a. Type 2 stage reinforced concrete riser
- b. Location 125 ft. from the left abutment
- c. Entrance Inverts El. 968.0 ft. M.S.L. (low-level intake);
- d. Exit Inverts El. 944.0 ft. M.S.L. El. 980.7 ft. M.S.L.  
(upper-level intake)
- e. Emergency Drawdown Facilities 18 in. drain pipe, entrance  
invert at El. 948.2 ft. M.S.L.

HYDROMETEOROLOGICAL GAGES: None

- a. Type \_\_\_\_\_
- b. Location \_\_\_\_\_
- c. Records \_\_\_\_\_

MAXIMUM NON-DAMAGING DISCHARGE No records available

APPENDIX C

PHOTOGRAPH LOCATION PLAN AND PHOTOGRAPHS

## DETAILED PHOTOGRAPH DESCRIPTIONS

### Overall View -

Top Photo - Overall View of the Upstream Face of the  
(OV-T) Dam from the Right Abutment

Bottom Photo - Overall View of the Downstream Face of  
(OV-B) the Dam from the Emergency Spillway

### Photograph Location Plan

Photo 1 - View of the Riser Unit, Reservoir, and Right Abutment

Photo 2 - View of the Impact Basin

Photo 3 - View of the Downstream Channel from the Crest of the Dam

Photo 4 - View of Water Collecting at the Toe of the Bench on the Downstream Site of the Embankment


Photo 5 - View of the Emergency Spillway Looking Upstream

Photo 6 - View of the Slumping Area on the Right Side of the Emergency Spillway

Photo 7 - View of the Slumping Areas and Erosion on the Right Abutment Above the Emergency Spillway

Photo 8 - View of the Slumped Area at the Downstream End of the Emergency Spillway

Note: Photographs were taken on 27 March 1980.



# PHOTOGRAPH LOCATION PLAN

PA 480  
 NDI No. PA01125  
 PENN. No. 63-84  
 SCS No. PA480  
 INSPECTED 27 MARCH 1980

SCHEMATIC: NOT TO SCALE



PHOTO 1. View of the Riser Unit, Reservoir, and Right Abutment




PHOTO 2. View of the Impact Basin




PHOTO 3. View of the Downstream Channel from the Crest of the Dam




PHOTO 4. View of Water Collecting at the Toe of the Bench on the Downstream Side of the Embankment



PHOTO 5. View of the Emergency Spillway Looking Upstream



PHOTO 6. View of the Slumping Area on the Right Side of the Emergency Spillway



**PHOTO 7. View of the Slumping Areas and Erosion on the Right Abutment  
above the Emergency Spillway**



**PHOTO 8. View of the Slumped Area at the Downstream End of the  
Emergency Spillway**



APPENDIX D

HYDROLOGIC AND HYDRAULIC COMPUTATIONS

MICHAEL BAKER, JR., INC.  
THE BAKER ENGINEERS

Box 280  
Beaver, Pa. 15009

Subject PA-980 S.O. No. \_\_\_\_\_  
APPENDIX D - HYDROLOGIC AND Sheet No. \_\_\_\_\_ of \_\_\_\_\_  
HYDRAULIC COMPUTATIONS Drawing No. \_\_\_\_\_  
Computed by \_\_\_\_\_ Checked by \_\_\_\_\_ Date \_\_\_\_\_

<u>SUBJECT</u>	<u>PAGE</u>
HYDROLOGY AND HYDRAULIC DATA BASE	1
REMARKS	2
HYDROLOGIC DATA	3
STAGE VS. STORAGE, AREA DATA	4
STAGE VS. DISCHARGE DATA	4
TOP OF DAM PROFILE AND TYPICAL CROSS-SECTION	5
DRAINAGE BASIN MAP	6

# HYDROLOGY AND HYDRAULIC ANALYSIS DATA BASE

NAME OF DAM: PA 480

PROBABLE MAXIMUM PRECIPITATION (PMP) = 24.1 INCHES/24 HOURS<sup>(1)</sup>

STATION	1	2	3	4	5
Station Description	PA 480				
Drainage Area (square miles)	1.09				
Cumulative Drainage Area (square miles)	1.09				
Adjustment of PMF for Drainage Area (%) <sup>(2)</sup>	Zone 7				
6 Hours	102				
12 Hours	120				
24 Hours	130				
48 Hours	140				
72 Hours	-				
Snyder Hydrograph Parameters					
Zone (3)	28B				
C <sub>p</sub> /C <sub>t</sub> <sup>(4)</sup>	0.57/1.7				
L (miles) (5)	1.44				
L <sub>ca</sub> (miles) (5)	0.30				
t <sub>p</sub> = C <sub>t</sub> (L·L <sub>ca</sub> ) <sup>0.3</sup> (hours)	1.32				
Spillway Data					
Crest Length (ft)	(Spillway rating curve included on sheet 4)				
Freeboard (ft)					
Discharge Coefficient					
Exponent					

(1) Hydrometeorological Report 33 (Figure 1), U.S. Army, Corps of Engineers, 1956.

(2) Hydrometeorological Report 33 (Figure 2), U.S. Army, Corps of Engineers, 1956.

(3) Hydrological zone defined by Corps of Engineers, Baltimore District, for determining Snyder's Coefficients (C<sub>p</sub> and C<sub>t</sub>).

(4) Snyder's Coefficients.

(5) L = Length of longest water course from outlet to basin divide.

L<sub>ca</sub> = Length of water course from outlet to point opposite the centroid of drainage area.

MICHAEL BAKER, JR., INC.  
THE BAKER ENGINEERS

Box 280  
Beaver, Pa. 15009

Subject PA-480

S.O. No. \_\_\_\_\_

REMARKS

Sheet No. 2 of 6

Drawing No. \_\_\_\_\_

Computed by WDL

Checked by \_\_\_\_\_

Date 5-21-80

PA-480 WAS DESIGNED BY THE SCS IN ACCORDANCE WITH STANDARD CRITERIA. THE DESIGN FLOOD USED TO DETERMINE THE TOP OF DAM ELEVATION IS BASED ON RAINFALL ESSENTIALLY EQUAL TO THE PROBABLE MAXIMUM PRECIPITATION (PMP). THE DAM SHOULD THEREFORE BE CAPABLE OF PASSING THE PMF WITHOUT OVERTOPPING. IN VIEW OF THE ABOVE, NO ADDITIONAL HYDROLOGIC OR HYDRAULIC CALCULATIONS WERE PERFORMED FOR THIS REPORT.

THE SDF SELECTED IN SECTION 5 OF THIS REPORT IS THE 1/2 PMF. THE CREST OF THE EMERGENCY SPILLWAY WAS PLACED AT THE ELEVATION THE RESERVOIR LEVEL WOULD REACH DURING THE 100-YEAR FLOOD. THEREFORE, THERE WILL BE FLOW IN THE EMERGENCY SPILLWAY DURING THE SDF. USING SCS DESIGN INFORMATION, IT IS ESTIMATED THAT THE MAXIMUM DEPTH OF FLOW IN THE EMERGENCY SPILLWAY DURING THE 1/2 PMF IS 7.6 FT; THE MAXIMUM FLOW VELOCITY IS 7.8 FT/SEC, AND THE TOTAL DURATION OF FLOW IN THE EMERGENCY SPILLWAY IS APPROXIMATELY 6 HOURS. THE ROCK AND EARTH INTO WHICH THE EMERGENCY SPILLWAY IS CUT SHOULD NOT BE SERIOUSLY AFFECTED BY THIS FLOW.

THE SPILLWAY IS THEREFORE CONSIDERED TO BE "ADEQUATE" ACCORDING TO THE RECOMMENDED CRITERIA.

MICHAEL BAKER, JR., INC.

THE BAKER ENGINEERS

Box 280  
Beaver, Pa. 15009

Subject PA-480

HYDROLOGIC DATA

Computed by WDL

S.O. No. \_\_\_\_\_

Sheet No. 3 of 6

Drawing No. \_\_\_\_\_

Checked by \_\_\_\_\_ Date 5-21-80

INFORMATION FROM THE SCS DESIGN REPORT FOR PA-480:

DRAINAGE AREA = 1.09 SQ. MI.

TIME OF CONCENTRATION = 0.61 HRS.

STORM DURATION = 6 HRS.

RUNOFF CURVE NUMBERS:

DESIGN HYDROGRAPH (AMC II) CN = 88

FREBOARD HYDROGRAPH (AMC II) CN = 74

HYDROGRAPH	RAINFALL (IN)	RUNOFF (IN)	PEAK INFLOW (CFS)
EMERGENCY SPILLWAY	9.7	6.47	645
FREBOARD	25.5	21.72	6876

FROM HMR-33, 6 HOUR PMP = 24.6 IN.

MICHAEL BAKER, JR., INC.  
THE BAKER ENGINEERS

Box 280  
Beaver, Pa. 15009

Subject PA - 480 S.O. No. \_\_\_\_\_  
STAGE VS. STORAGE AREA DATA Sheet No. 4 of 6  
Drawing No. \_\_\_\_\_  
Computed by WDL Checked by \_\_\_\_\_ Date 5-21-80

THE FOLLOWING INFORMATION IS FROM THE SCS DESIGN REPORT FOR PA-480:

STAGE (FT)	STORAGE (ACRE-FT)	AREA (ACRES)
968.0	0	3.6
970.0	6.8	4.14
975.0	28.5	5.04
980.0	56.1	6.53
985.0	91.5	8.12
990.0	136.0	10.21
995.0	191.3	12.43
1000.0	258.1	14.50
1005.0	337.0	17.06
1010.0	428.0	19.36
1015.0	531.0	22.08



DISCHARGE RATING


STAGE (FT)	DISCHARGE (CFS)	REMARKS
968.0	0	NORMAL POOL ELEVATION
970.0	5.77	
975.0	11.7	
980.0	15.4	
980.7	15.9	CREST OF UPPER LEVEL INTAKE
985.0	122.16	
990.0	129.22	
995.0	135.2	
997.1	138.7	CREST OF EMERGENCY SPILLWAY
1000.0	142.3	
1000.2	627	DESIGN HIGH WATER
1002.0	1635	
1010.0	6846	TOP OF DAM

MICHAEL BAKER, JR., INC.  
THE BAKER ENGINEERS

Box 280  
Beaver, Pa. 15009

Subject PA 480 S.O. No. \_\_\_\_\_  
TOP OF DAM PROFILE AND Sheet No. 5 of 6  
TYPICAL CROSS-SECTION Drawing No. \_\_\_\_\_  
Computed by WDL Checked by \_\_\_\_\_ Date 4-28-80





DRAINAGE BASIN MAP  
PA 480

QUADS :  
1. AVELLA

2000 0 2000 4000  
SCALE





APPENDIX E


PLATES

## CONTENTS

- Plate 1 - Location Plan
- Plate 2 - Watershed Map
- Plate 3 - Plan of Structural Works
- Plate 4 - Emergency Spillway
- Plate 5 - Fill Placement
- Plate 6 - Cut-off Trench
- Plate 7 - Drainage
- Plate 8 - Grouting
- Plate 9 - Principal Spillway Profile
- Plate 10 - Riser
- Plate 11 - Impact Basin












PLATE 3

THESE ARE THE  
ORIGINAL SURVEY  
MAPS OF THE  
LANDS OF THE  
GOVERNMENT  
IN THE STATE OF  
ALABAMA  
AND THE  
TERRITORY OF  
FLORIDA  
AND THE  
TERRITORY OF  
LOUISIANA  
AND THE  
TERRITORY OF  
MISSISSIPPI  
AND THE  
TERRITORY OF  
ARKANSAS  
AND THE  
TERRITORY OF  
KENTUCKY  
AND THE  
TERRITORY OF  
TENNESSEE  
AND THE  
TERRITORY OF  
VIRGINIA  
AND THE  
TERRITORY OF  
WEST VIRGINIA  
AND THE  
TERRITORY OF  
OHIO  
AND THE  
TERRITORY OF  
INDIANA  
AND THE  
TERRITORY OF  
ILLINOIS  
AND THE  
TERRITORY OF  
MICHIGAN  
AND THE  
TERRITORY OF  
WISCONSIN  
AND THE  
TERRITORY OF  
MINNESOTA  
AND THE  
TERRITORY OF  
IOWA  
AND THE  
TERRITORY OF  
NEBRASKA  
AND THE  
TERRITORY OF  
KANSAS  
AND THE  
TERRITORY OF  
OKLAHOMA  
AND THE  
TERRITORY OF  
NEW MEXICO  
AND THE  
TERRITORY OF  
ARIZONA  
AND THE  
TERRITORY OF  
CALIFORNIA  
AND THE  
TERRITORY OF  
NEVADA  
AND THE  
TERRITORY OF  
UTAH  
AND THE  
TERRITORY OF  
IDAHO  
AND THE  
TERRITORY OF  
MONTANA  
AND THE  
TERRITORY OF  
WYOMING  
AND THE  
TERRITORY OF  
COLORADO  
AND THE  
TERRITORY OF  
UTAH  
AND THE  
TERRITORY OF  
NEVADA  
AND THE  
TERRITORY OF  
CALIFORNIA  
AND THE  
TERRITORY OF  
ARIZONA  
AND THE  
TERRITORY OF  
NEW MEXICO  
AND THE  
TERRITORY OF  
OKLAHOMA  
AND THE  
TERRITORY OF  
KANSAS  
AND THE  
TERRITORY OF  
NEBRASKA  
AND THE  
TERRITORY OF  
IOWA  
AND THE  
TERRITORY OF  
MINNESOTA  
AND THE  
TERRITORY OF  
WISCONSIN  
AND THE  
TERRITORY OF  
MICHIGAN  
AND THE  
TERRITORY OF  
ILLINOIS  
AND THE  
TERRITORY OF  
INDIANA  
AND THE  
TERRITORY OF  
OHIO  
AND THE  
TERRITORY OF  
WEST VIRGINIA  
AND THE  
TERRITORY OF  
VIRGINIA  
AND THE  
TERRITORY OF  
TENNESSEE  
AND THE  
TERRITORY OF  
KENTUCKY  
AND THE  
TERRITORY OF  
ARKANSAS  
AND THE  
TERRITORY OF  
LOUISIANA  
AND THE  
TERRITORY OF  
FLORIDA  
AND THE  
TERRITORY OF  
ALABAMA






**PLATE 4**

HARMON CREEK WATERSHED  
 FLOOD WATER RETENTION DAM NO. 4  
 WASHINGTON COUNTY, PENNSYLVANIA  
 EMERGENCY SPILLWAY  
 U.S. DEPARTMENT OF AGRICULTURE  
 SOIL CONSERVATION SERVICE  
 WASHINGTON, D. C.  
 1952

2






TYPICAL SECTION




TYPICAL SECTION

ALL


[illegible]



**TYPICAL SECTION OF DAM**



**TYPICAL SECTION OF DIKE**



- CONSTRUCTION NOTES**
1. Excavate and fill with compacted earth to 10 ft depth.
  2. Excavate and fill with compacted earth to 10 ft depth.
  3. Excavate and fill with compacted earth to 10 ft depth.
  4. Excavate and fill with compacted earth to 10 ft depth.
  5. Excavate and fill with compacted earth to 10 ft depth.


**PLATE 5**

HARMON CREEK WATERSHED  
 FOR WATER RESOURCES  
 WA - HARMON CREEK WATERSHED  
 FILL PLACEMENT  
 SUBMITTAL OF FILL PLACEMENT  
 SOIL CONSERVATION SERVICE  
 1/1/1971  
 1/1/1971


2







PLAN VIEW



SECTION A-A

GRAND NATIONAL BANK

[illegible]

- 


SECTION C-C

100-443887-100

- [illegible]



HARMON CREEK WATERSHED  
 ESTABLISHED BY THE NATIONAL  
 FOREST SERVICE, U.S. DEPARTMENT OF AGRICULTURE  
 SPRING 1906  
 U.S. FOREST SERVICE, NATIONAL FOREST  
 SOIL CONSERVATION SERVICE  
 1960  
 2



ITS FOR GRAD











# PRINCIPAL SPILLWAY

## CONSTRUCTION NOTES

1. All construction shall be in accordance with the specifications for the project.

## PLATE 9

NOT TO SCALE

HAWK CREEK WATER TOWER

1. All construction shall be in accordance with the specifications for the project.

2. All construction shall be in accordance with the specifications for the project.

3. All construction shall be in accordance with the specifications for the project.

4. All construction shall be in accordance with the specifications for the project.

5. All construction shall be in accordance with the specifications for the project.

6. All construction shall be in accordance with the specifications for the project.

7. All construction shall be in accordance with the specifications for the project.

8. All construction shall be in accordance with the specifications for the project.

9. All construction shall be in accordance with the specifications for the project.

10. All construction shall be in accordance with the specifications for the project.

11. All construction shall be in accordance with the specifications for the project.

12. All construction shall be in accordance with the specifications for the project.


13. All construction shall be in accordance with the specifications for the project.

14. All construction shall be in accordance with the specifications for the project.

15. All construction shall be in accordance with the specifications for the project.

16. All construction shall be in accordance with the specifications for the project.


17. All construction shall be in accordance with the specifications for the project.



Gate Hole Frame

Gate Stem Sleeve -  
Size and location  
to accommodate  
gate stem pulled

PLAN - TOP



Ball and Flange Wall Fitting -  
Detail sheet 8

Low Stage  
Trash Rack  
Details sheet 23

Invert  
E 968.0

Sub-Bedding

STANDARD COVERED RISER

DESIGNED BY: [Signature]  
CHECKED BY: [Signature]  
DATE: 10/1/55

STANDARD DRAWING NO. 300-1

DATE



4 x 6 Drip Steel etc.  
 1/2 inch to 1/4 inch  
 1/2 inch to 1/4 inch  
 1/2 inch to 1/4 inch  
 1/2 inch to 1/4 inch  
 1/2 inch to 1/4 inch  
 1/2 inch to 1/4 inch



PLATE  
 CONSTR. JOINT



CONSTR. JOINT



721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32
33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64
65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80
81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96
97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112
113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128
129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144
145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160
161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176
177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192
193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208
209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224
225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240
241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256
257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272
273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288
289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304
305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320
321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336
337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352
353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368
369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384
385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400
401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416
417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432
433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448
449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464
465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480
481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496
497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512
513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528
529	530	531	532	533	534	535	536	537	538	539	540	541	542	543	544
545	546	547	548	549	550	551	552	553	554	555	556	557	558	559	560
561	562	563	564	565	566	567	568	569	570	571	572	573	574	575	576
577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592
593	594	595	596	597	598	599	600	601	602	603	604	605	606	607	608
609	610	611	612	613	614	615	616	617	618	619	620	621	622	623	624
625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640
641	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656
657	658	659	660	661	662	663	664	665	666	667	668	669	670	671	672
673	674	675	676	677	678	679	680	681	682	683	684	685	686	687	688
689	690	691	692	693	694	695	696	697	698	699	700	701	702	703	704
705	706	707	708	709	710	711	712	713	714	715	716	717	718	719	720
721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736


PLATE 10

HARMON CREEK WATERSHED  
 A. J. HARMON, JR., OWNER  
 WASHINGTON, D. C.  
 U. S. DEPARTMENT OF AGRICULTURE  
 SOIL CONSERVATION SERVICE




Excursion Limit  
Material


Note: East section  
of conduit to be  
laid horizontal



SECTION ON CENTERLINE



SECTION A  
NOT TO SCALE



CONSTRUCTION JOINT DETAILS  
NOT TO SCALE

PLATE II

QUANTITIES

Formwork (Sheet piers)	1900 sq. ft.
Reinforcing Concrete (Just 40' 10')	45.00 cu. yd.
Reinforcing Steel	6.45 tons
Drainage	
10" Drain Pipe, Reinforced, Asbestos-Treated, Type III, Class B, Pressure Pipe	500.00 ft.
6" Drain Pipe, Reinforced, Asbestos-Treated, Type III, Class B, Pressure Pipe	100.00 ft.
Drain Pipe Tees	2.00
Drain Pipe 90° Elbs	2.00
Drain Pipe 45° Elbs	2.00
Drain Pipe Fittings	2.00
1/4" x 6" Carbon steel plate, Structural grade	76.00 lbs.



HARMON CREEK WEIR AND  
FLOODGATE WITH 10' 10" HEADWALL  
AND 10' 10" WINGWALLS  
PROJECT NO. 100-100  
U.S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE  
PROJECT NO. 100-100  
DATE: 10/1/54  
BY: J. H. HARRIS

APPENDIX F

REGIONAL GEOLOGY

### REGIONAL GEOLOGY

PA 480 Dam is located in the Pittsburgh Plateaus Section of the Appalachian Plateaus Physiographic Province. Bedrock units below the dam are contained in the Casselman formation of the Conemaugh group, Pennsylvanian system. The Casselman formation consists of cyclic sequences of sandstone, shale, redbeds, and thin limestone and coal.

The Pittsburgh coal (base of Monongahela group) is located in the emergency spillway at approximate Elevation 1073 feet M.S.L. The Pittsburgh coal is approximately six feet thick in the area and has been strip mined immediately above the emergency spillway on the right abutment. The lower half of the spillway is in the Pittsburgh limestone member of the Conemaugh group and consists of thin limestone and sandstone zones and fractured and jointed shales and siltstones. The abutments are composed of the Connellsville, Clarksburg, and Morgantown members of the Conemaugh group. The Connellsville sandstone is exposed on the left abutment and shows jointing and fracturing. High permeabilities were noted during the exploration program in the Connellsville sandstone and the bedrock of the Connellsville sandstone member along the centerline of the dam in the right abutment and below the emergency spillway cut was grouted during construction. The bedrock below the floodplain consists of shales and sandstones of the Morgantown member.

The abutment soils consist of residual and colluvial gravels, silts, and clays. In the floodplain, alluvial, residual, and some colluvium were present to a maximum depth of 25.5 feet. These soils included clayey silts, silty and gravelly clays, and clayey gravels.

A regional geologic map and legend are presented on the following pages. Additional site geology can be obtained by reviewing the "Detailed Geologic Investigation Report" in the SCS design folder for this dam.





# GEOLOGY MAP LEGEND

## GROUP FORMATION

## DESCRIPTION

Alluvium		Ot	Sand, gravel, clay.
Terrace deposits			Sand, clay, gravel on terraces above present rivers; includes Carmichaels Formation.
DUNKARD	Greene		Cyclic sequences of sandstone, shale, red beds, thin limestones and coals.
	Washington	Pw	Cyclic sequences of sandstone, shale, limestone, and coal; contains Washington coal bed at base.
	Waynesburg		Cyclic sequences of sandstone, shale, limestone and coal; contains Waynesburg coal bed at base.
MONONGAHELA		Pm	Cyclic sequences of shale, limestone, sandstone and coal; contains Pittsburgh coal bed at base.
P. CONEAUGH	Casselman	Pcc	Cyclic sequence of sandstone, shale, red beds and thin limestone and coal.
	Ames		
	Glenshaw	Pcg	Cyclic sequences of sandstone, shale, red beds and thin limestone and coal; several fossiliferous limestone; Ames limestone bed at top.
ALLEGHENY	Vanport	Pa	Cyclic sequences of shale, sandstone, limestone, and coal; contains Brookville coal at base and Upper Freeport coal at top; within group are the commercial Vanport limestone and Kittanning and Clarion coals.
		Pa	
POTTSVILLE		Pp	Sandstone and shale; contains some conglomerate and locally mineable coal.
Mauch Chunk		Mch	Red and green shale with some sandstone; contains Wymys Gap and Loyalhanna limestones.
Pocono			Sandstone and shale with Burgoon sandstone at top.